

Exh. GMP-MB-12

High-Level Overview of EJG7

ZOI Projects

EJG7 Circuit - ZOI Projects

District: Brattleboro
 Total Customers (approx.) 2648
 20 Least Reliable Rank (2023) 1
 Average Pole Age 33

Line / Road Name	Length(miles)	Town	Circuit	Expected Construction Type*	single/three	Zone	Est. Cost OH	Est. Cost UG
L3-P794-749 - Rt 35	1.4	Townsend	EJ-G7	Spacer	3	2	980000	
L3-P749 to end Rt 35	3.1	Townsend	EJ-G7	CIC	1	3		930000
L303-East Hill Rd	1.1	Townsend	EJ-G7	CIC	1	3		330000
LVH4A12-A12G Newfane Rd/S Wardsboro Rd to L65	2.5	Newfane	EJ-G7	CIC	1	3		750000
L55-P1-Windham Hill Rd	2	Jamaica	EJ-G7	CIC	1	3		600000
L72-South Hill Rd	2	Jamaica	EJ-G7	CIC	1	3		600000
Pike Falls Area Loop-L5012, 50128	8	Jamaica	EJ-G7	CIC	1	3		2400000
L74-P1 thru P53 Stratton Arlington Rd	3	Stratton	EJ-G7	CIC	1	3		900000
L7-P243 thru P276 Rt. 100-Cross Rd	1.5	Jamaica	EJ-G7	CIC	1	3		450000
LVH4A15-P3-So Wardsboro Rd	2.65	Wardsboro	EJ-G7	CIC	1	3		795000
Rt . 30-Main Line feed	12.5	Jamaica/Townsend/Newfane	EJ-G7	Spacer	3	1	8750000	
L7-Route 100	9	Jamaica / Wardsboro	EJ-G7	Spacer	3	2	6300000	
L742-W Jamaica Rd P1-P51	3	Stratton	EJ-G7	CIC	1	3		
L702/7022-P1-7 & P1-P17	1.2	Wardsboro	EJ-G7	Spacer	3	2	840000	
L501	3	Jamaica	EJ-G7	CIC	1	3		900000
LVH4A-A13 Tomlinson Rd	1.3	Wardsboro	EJ-G7	CIC	1	3		390000
L53-Turkey Mtn Rd	2.9	Jamaica	EJ-G7	CIC	1	3		870000
L32-Plumb Rd, Taft Rd, Brookline Rd P1- P68	3	Townsend	EJ-G7	CIC	1	3		900000
L321, Crane Mtn Rd P1-P27	1.1	Townsend	EJ-G7	CIC	1	3		330000
L31, Peaked Mtn Rd P1-P31	1.3	Townsend	EJ-G7	CIC	1	3		390000
L306-Deer Valley Rd P1-P30	1.6	Townsend	EJ-G7	CIC	1	3		480000
L70221/L70223-Sawmill Rd	1	Wardsboro	EJ-G7	CIC	1	3		300000
L70225-P1 thru P17	1	Wardsboro	EJ-G7	CIC	1	3		300000
L7022-P18 thru P11 Sheldon hill	0.5	Wardsboro	EJ-G7	CIC	1	3		150000
L702252-Oak Hill Rd/Silver Ln P1 - P10	0.5	Wardsboro	EJ-G7	CIC	1	3		150000
L7022521-P1 - P11	0.5	Wardsboro	EJ-G7	CIC	1	3		150000
L7- P276-P293 Pike Hollow Rd	1	Wardsboro	EJ-G7	CIC	1	3		300000
LVH4A-P102X - P140 East Dover Road-North St	3	Wardsboro / Dover	EJ-G7	CIC	1	3		900000
LVH4A-Current project 3-phase P1 - P86	5.25	Townsend / Wardsboro	EJ-G7	CIC	3	2		3675000
LVH4A-Current project 2-phase P86-P102X	1.6	Wardsboro	EJ-G7	CIC	3	2		1120000
							\$ 16,870,000.00	\$ 19,060,000.00
Circuit Total							198	
Total Estimated Existing Storm hardened							109	
							Storage Installations	
								\$ 10,010,000.00
Estimated ZOI Circuit Projects								\$ 45,940,000.00
UG Miles							57.4	
Total Spacer Miles							24.1	
Est. Zone 4 Customers (Storage)							455	

*Note for CIC construction, occasional overhead construction will be employed as required by conditions in the field.